



Camino Real Regional Mobility Authority

John Hayes St. Extension Phase I Project CSJ # 0924-06-564

Questions & Answers

July 20, 2023

**JOHN HAYES ST. EXTENSION PHASE I PROJECT
QUESTIONS AND ANSWERS
POSTED – JULY 20, 2023**

1. Can you provide electronic copies of the cross sections, time determination schedule, and geotechnical report?

Yes, cross sections, a time determination schedule, and a geotechnical report have been added to the Procurements Page of the CRRMA website: www.crrma.org.

2. Can you confirm the scope of work for item 351-6004 Flexible Pavement Repair 8" is the temporary compacted subgrade on plan sheets 24 & 29?

Yes, item 351-6004 is the item number for the Temporary Compacted Subgrade.

3. There is a detail on sheet 105 and a detail on sheet 121 for the CRCP to ACP transitions, which detail will be used for this project?

Use CRCP to ACP transitions on sheet 121.

4. How is the partial 5' mill section shown in Detail B of the typical sections paid for?

This item is paid under item 105-6015.

5. Can you provide more information for 423-ELP1 Retaining Wall (Stone)? Sheet 108 has 3 different sections that are dependent on the proposed wall height. Is there a profile drawing of the wall or can you provide the wall height for the 656' of Wall?

Different details are provided to address the changes in elevation. Use roadway plan and profile as well as cross section to determine which wall height detail to use.

6. Can you post a bidder's list to let Subcontractors and Material Vendors know who is bidding the project?

Yes, a bidder's list has been added to the Procurements Page of the CRRMA website: www.crrma.org.

7. What forms will be required for the bid submission? Volume I contains documents that are provided after the bid i.e. payment bond and contract.

All forms and documents in Proposal Volume I of II shall be submitted at the time of bid submission but the following forms can be left blank:

H. Payment Bond
N. Contract

8. There is a significant amount of waste/garbage throughout the ROW. Will this be cleaned prior to the start of construction or will the contractor be required to clean waste/garbage? If the contractor, then how is this work paid for? Prep ROW covers the removal of structures but does not address waste/garbage.

No, ROW will not be cleaned prior to construction. This work falls under “debris” which is called out and paid under Item 100 Preparing Right of Way Specification.

9. There is a discrepancy on the cross section plans that were uploaded to the CRRMA website. Vertical scale is off and doesn't match up with the scale provided. I also tried to calibrate it to the 5' increments vertically however it reverts to the 10' mark. Can you please clarify the correct scale or provide new cross sections with an accurate scale or revised plans that show the correct dimensions?

Horizontal and Vertical scales for the earthwork cross sections have been verified. Scale for the Horizontal cross section is 1" = 30'. The Vertical exaggeration is half of the Horizontal dimension. Therefore, if the Vertical scale is 10' then the actual Vertical dimension is 5'. Cross sections sheets were printed out on 11"x17" format and checked with the designated scales and the values match. Cross sections were developed as per TxDOT standards.

[END OF Q&A DOCUMENT]